



CITY OF DAHLONEGA
465 Riley Road
Dahlonega, Georgia 30533
Phone: 706-864-6133 • Fax: 706-864-4837

OLIVER DRIVE DRAINAGE IMPROVEMENTS PROJECT 2021-011

ADDENDUM 1

Addendum Issue Date: Tuesday, October 27, 2021

Addendum Subject: Responses to Contractor Questions

Bidders must take due notice and be governed accordingly. The addendum must be acknowledged as indicated in the Invitation to Bid or your Bid may not be considered.

REVISED ATTACHMENT D AND CONTRACT WILL BE POSTED BY 12:00 PM OCTOBER 28, 2021

CONTRACTOR QUESTIONS AND ANSWERS:

1. Is there an area that can be used for staging equipment and materials? **The City has permission from landowner to use area on project the first pull off on left that is approximately 70 ft wide x 140 ft long. When project is completed, Contractor shall restore to original condition.**
2. Will unit pricing for rock removal be added to the bid form? **This will be included in the Grading Complete item.**
3. Will a unit price quantity be added to the bid form for the asphalt driveway apron proposed per plans, page 4? Can a detail be provided? **We will increase the quantity of the existing GAB and Asphalt item if needed.**
4. Will concrete trench cap, and asphalt milling/asphalt removal be added to bid form? **Asphalt removal should be included in the Grading Complete item. Will add concrete bid item.**
 - a. Where do we add the cost for these items and how do we know how much asphalt paving/patching will be required if the existing storm drain line at Wimpy Mill Rd has to be replaced? **At this time, paving quantities are still estimated. Base your bids on the estimate provided. However, asphalt is bid as a unit cost and will be paid for by the ton.**
 - b. Will the entire intersection be repaved? **Possibly, field conditions will dictate the amount of paving to be completed. Again, payment is made by the ton.**
5. Regarding the proposed 36" headwall, there is a 6" pvc pipe exposed at the edge of the road and an 8" arial dip sewer pipe directly under the bridge. Can a detail be provided showing the location of the existing pipes, bridge, and proposed location of headwall? **At this time, all available data is shown on the bid documents.**
 - a. The plan basically shows the headwall under the bridge, is it anticipated to remove the bridge for the headwall installation? **No. The headwall will be very near the edge of the bridge, but removal of the bridge does not appear to be required.**
 - b. What is the minimum distance the headwall can be from the edge of pavement? **Bid documents indicate a clear shoulder of 8'.**